

**Estimate #:** 1003.00  
**Date:** 01/17/2011  
**Terms:** Due on Receipt  
**PO #:** 1810  
**Sales Rep:** Dan  
**Print Date:** 03/10/2011

**Customer Name:**  
 Ralph Wood  
 330 3rd Ave  
 Nisula, MI 49952

**Job Name:**  
 330 3rd Ave  
 330 3rd Ave  
 Nisula, MI 49952  
 P: 555-8772                      A: 555-9250

<u>Item ID</u>	<u>Description</u>	<u>Qty</u>	<u>Rate</u>	<u>Total</u>
HOUSE PACKAGE:		Package Accepted (please circle one): YES / NO		
A12	~ 12" Flat Attic: Install insulation to 12" (R-44) with cellulose insulation.	728	\$0.89	\$647.92
<i>Upgrade: ~ 14" Flat Attic: Install insulation to 14" (R-50) in open flat attic</i>			\$65.52	Initial: _____
RW	~ Rafterwall: Install insulation in rafterwall area. (sloped ceiling area below open attic)	410	\$1.00	\$410.00
CATH	~ Vented Cathedral: Install insulation in vented cathedral ceiling.	812	\$1.60	\$1,299.20
CHAN	~ Vent Chutes: Install channel vent chutes in every truss opening.	248	\$2.50	\$620.00
W4	~ 4" Sidewalls: Install sprayed cellulose in 4" exterior sidewalls.(R-13)	961	\$0.65	\$624.65
W6	~ 6" Sidewalls: Install sprayed cellulose in 6" exterior sidewalls.(R-21)	2,288	\$0.79	\$1,807.52
W6 Walkout/Da	~ 6" Walkout/Daylight walls: Install sprayed cellulose in 6" exterior walkout/daylight basement sidewalls. (R-21)	346	\$0.79	\$273.34
FOAM	~ Foamboard: R-board type ceilings/backer installed in kneeattic/kneewall areas	6	\$18.00	\$108.00
BOX	~ Boxesill/Rimjoist: Boxesill/Rimjoist insulation (areas with unfinished ceilings may be insulated with fiberglass)	169	\$1.00	\$169.00
<b>HOUSE PACKAGE TOTAL: \$5,959.63 (Package Is Included In Total)</b>				
BONUS ROOM PACKAGE:		Package Accepted (please circle one): YES / NO		
BA12	~ Bonus Room Attic: Install insulation in attic area of bonus room.	895	\$1.10	\$984.50
AF	~ Attic/Floor area: Install insulation in attic and under floor. Eg: Above garage below bonus room.	574	\$1.00	\$574.00
CHAN	~ Vent Chutes: Install channel vent chutes in every truss opening.	96	\$2.50	\$240.00
W4	~ 4" Sidewalls: Install sprayed cellulose in 4" exterior sidewalls.(R-13)	656	\$0.65	\$426.40
FOAM	~ Foamboard: R-board type ceilings/backer installed in kneeattic/kneewall areas	12	\$18.00	\$216.00
<b>BONUS ROOM PACKAGE TOTAL: \$2,440.90 (Package Is Included In Total)</b>				
GARAGE WALL PACKAGE:		Package Accepted (please circle one): YES / NO		
W6	~ 6" Sidewalls: Install sprayed cellulose in 6" exterior sidewalls.(R-21)	641	\$0.79	\$506.39
<b>GARAGE WALL PACKAGE TOTAL: \$506.39 (Package Is NOT Included In Total)</b>				

Thanks For Your Business!

We will contact you as soon as we schedule your job. Don't hesitate to contact us if you have any questions.

# Estimate

Page 2 of 2

**S** SMITH INSULATION, INC.  
 123 ANY STREET, ANYTOWN, MI 69999  
 PHONE: (222) 333-5678  
 FAX: (222) 333-5678  
**I** EMAL: JIM@SMITHINSULATION.COM  
 WWW.SMITHINSULATION.COM  
 Professional Insulation Services Since 1970

**Estimate #:** 1003.00  
**Date:** 01/17/2011  
**Terms:** Due on Receipt  
**PO #:** 1810  
**Sales Rep:** Dan  
**Print Date:** 03/10/2011

<b>Customer Name:</b> Ralph Wood 330 3rd Ave Nisula, MI 49952	<b>Job Name:</b> 330 3rd Ave 330 3rd Ave Nisula, MI 49952 P: 555-8772	A: 555-9250
--	---	-------------

Subtotal: \$8,400.53

\_\_\_\_\_  
AUTHORIZED SIGNATURE DATE

Sales Tax: \$504.03

\_\_\_\_\_  
SIGNATURE PRINT NAME DATE

Grand Total: \$8904.56