



Estimate

Page 1 of 1

Estimate #: 1003.00
Date: 01/17/2011
Terms: Due on Receipt
PO #: 1810
Sales Rep: Dan
Print Date: 03/10/2011

Customer Name: Ralph Wood 330 3rd Ave Nisula, MI 49952	Job Name: 330 3rd Ave 330 3rd Ave Nisula, MI 49952 P: 555-8772	A: 555-9250
<u>Description</u>		<u>Qty</u>
HOUSE PACKAGE: Package Accepted (please circle one): YES / NO		
~ 12" Flat Attic: Install insulation to 12" (R-44) with cellulose insulation.		728
<i>Upgrade: ~ 14" Flat Attic: Install insulation to 14" (R-50) in open flat attic</i>		\$65.52 Initial: _____
~ Rafterwall: Install insulation in rafterwall area. (sloped ceiling area below open attic)		410
~ Vented Cathedral: Install insulation in vented cathedral ceiling.		812
~ Vent Chutes: Install channel vent chutes in every truss opening.		248
~ 4" Sidewalls: Install sprayed cellulose in 4" exterior sidewalls.(R-13)		961
~ 6" Sidewalls: Install sprayed cellulose in 6" exterior sidewalls.(R-21)		2,288
~ 6" Walkout/Daylight walls: Install sprayed cellulose in 6" exterior walkout/daylight basement sidewalls. (R-21)		346
~ Foamboard: R-board type ceilings/backer installed in kneeattic/kneewall areas		6
~ Boxsill/Rimjoist: Boxsill/Rimjoist insulation (areas with unfinished ceilings may be insulated with fiberglass)		169
HOUSE PACKAGE TOTAL: \$5,959.63 (Package Is Included In Total)		
BONUS ROOM PACKAGE: Package Accepted (please circle one): YES / NO		
~ Bonus Room Attic: Install insulation in attic area of bonus room.		895
~ Attic/Floor area: Install insulation in attic and under floor. Eg: Above garage below bonus room.		574
~ Vent Chutes: Install channel vent chutes in every truss opening.		96
~ 4" Sidewalls: Install sprayed cellulose in 4" exterior sidewalls.(R-13)		656
~ Foamboard: R-board type ceilings/backer installed in kneeattic/kneewall areas		12
BONUS ROOM PACKAGE TOTAL: \$2,440.90 (Package Is Included In Total)		
GARAGE WALL PACKAGE: Package Accepted (please circle one): YES / NO		
~ 6" Sidewalls: Install sprayed cellulose in 6" exterior sidewalls.(R-21)		641
GARAGE WALL PACKAGE TOTAL: \$506.39 (Package Is NOT Included In Total)		

Thanks For Your Business!

We will contact you as soon as we schedule your job. Don't hesitate to contact us if you have any questions.

Subtotal: \$8,400.53

 AUTHORIZED SIGNATURE DATE

Sales Tax: \$504.03

 SIGNATURE PRINT NAME DATE

Grand Total: \$8904.56